

GPS #: **6134R1**

Date Destroyed:

Date Revised: 4/19/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 858/G-6

City / Location: Costa Mesa

Scale Factor: 0.99997143

Ellipsoid Red. Factor: 1.00000317

Combination Factor: 0.99997460

Convergence Angle: -00 55 34.86599

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 16.92798	117 56 08.71578	2192060.061	6048793.844	
2007.00	33 40 16.94437	117 56 08.73260	2192061.74	6048792.45	

References: RSB 150/10-23, CR 2001-0826

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "6134R1 3-01" FLUSH, IN LIEU OF PUNCHED ROUND HEAD SPIKE AND WASHER (NO STAMPING). MONUMENT WAS RESET PER CORNER RECORD # 2001-826. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF PLACENTIA AVE. AND ORIOLE DR.

