

GPS #: 6149R1

Date Destroyed:

Date Revised: 5/7/2003

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 858/J-7

City / Location: Costa Mesa

Scale Factor: 0.99997112

Ellipsoid Red. Factor: 1.00000222

Combination Factor: 0.99997334

Convergence Angle: -00 55 02.11814

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 06.10268	117 55 09.12199	2190884.952	6053812.223	
2007.00	33 40 06.11905	117 55 09.13878	2190886.63	6053810.83	

References: RSB 150/10-23, CR 2003-1091

Description:

FD PUNCHED SPIKE AND OCS WASHER STAMPED "6149R1" IN LIEU OF PUNCHED ROUND HEAD SPIKE WITH 1 1/2" BRASS WASHER (ILLEGIBLE). MONUMENT WAS RESET PER CORNER RECORD # 2003-1091 STATION IS LOCATED AT APPARENT CENTERLINE INTER OF HARBOR BLVD. AND MERRIMAC WAY.

