

GPS #: **6153R1**

Date Destroyed:

Date Revised: 7/11/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 888/G-1

City / Location: Costa Mesa

Scale Factor: 0.99997038

Ellipsoid Red. Factor: 1.00000175

Combination Factor: 0.99997214

Convergence Angle: -00 55 35.05196

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 39.71037	117 56 09.05423	2188299.065	6048704.422	
2007.00	33 39 39.72683	117 56 09.07101	2188300.75	6048703.03	

References: RSB 150/10-23, CR 2001-1150

Description:

FD PUNCHED SPIKE AND OCS BRASS WASHER STAMPED "6153R1 6-01" FLUSH, IN LIEU OF PUNCHED ROUND HEAD SPIKE WITH WASHER, STAMPED "RCE 12546 COSTA MESA". MONUMENT WAS RESET PER CORNER RECORD # 2001-1150. STATION IS LOCATED AT THE VISUAL CENTERLINE POINT OF REVERSE CURVE OF PLACENTIA AVE., 220'+/- NW'LY OF ESTANCIA (NORTH) APPARENT CENTERLINE. ESTANCIA NORTH IS THE NW ENTRANCE TO ESTANCIA HIGH SCHOOL.

