

GPS #: **6155R1**

Date Destroyed:

Date Revised: 4/19/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/A-7

City / Location: Costa Mesa

Scale Factor: 0.99997066

Ellipsoid Red. Factor: 1.00000206

Combination Factor: 0.99997272

Convergence Angle: -00 54 39.35215

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 49.81058	117 54 27.69292	2189182.498	6057287.078	
2007.00	33 39 49.82700	117 54 27.70966	2189184.18	6057285.69	

References: MM 455/33-35, RSB 150/10-23, CR 2001-0828

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "LS 5411" FLUSH, IN LIEU OF GEAR SPIKE, NO TAG. MONUMENT WAS RESET PER CORNER RECORD # 2001-828. STATION IS LOCATED AT CENTERLINE INTER OF FAIR DR. AND FAIRVIEW RD.

