

**GPS #:** **6161R1**

Date Destroyed:

Date Revised: 5/22/2003

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 860/A-6

City / Location: Irvine

Scale Factor: 0.99997135

Ellipsoid Red. Factor: 1.00000358

Combination Factor: 0.99997492

Convergence Angle: -00 52 12.30129

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 14.01347	117 50 00.09302	2191277.120	6079939.553	
2007.00	33 40 14.02999	117 50 00.10979	2191278.81	6079938.16	

References: RSB 150/10-23, CR 2003-1076, CR 2003-1622

**Description:**

FD 2" IP WITH 1 1/4" OCS TAG STAMPED "GPS 6161R1 5-03" DOWN 0.7' IN WELL, IN LIEU OF GEAR SPIKE AND WASHER (ILLEGIBLE). MONUMENT WAS RESET PER CR 2003-1076. STATION IS LOCATED IN THE INTERSECTION OF HARVARD AVE. AND MICHELSON DR.

