

GPS #: **6167**

Date Destroyed:

Date Revised: 3/25/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/H-7

City / Location: Irvine

Scale Factor: 0.99997089

Ellipsoid Red. Factor: 1.00000309

Combination Factor: 0.99997398

Convergence Angle: -00 52 53.54591

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 57.87824	117 51 15.14907	2189743.324	6073571.810	-64.514
2007.00	33 39 57.89470	117 51 15.16580	2189745.01	6073570.42	

References: MM 642/17-22, RSB 150/10-23, CR 2013-0193, CR 2013-2216, CR 2013-2343, CR 2013-3387

Description:

FD PUNCHED HEX BAR, DOWN 1.6' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF CAMPUS DR. AND JAMBOREE RD.

