

**GPS #:** 6168R1

Date Destroyed:

Date Revised: 4/19/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 859/F-7

City / Location: Newport Beach

Scale Factor: 0.99997053

Ellipsoid Red. Factor: 1.00000312

Combination Factor: 0.99997366

Convergence Angle: -00 53 11.97625

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 45.01018	117 51 48.68820	2188486.519	6070717.301	
2007.00	33 39 45.02660	117 51 48.70495	2188488.20	6070715.91	

References: MM 350/24-26, RSB 150/10-23, CR 2001-0830.

**Description:**

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "6168R1 3-01" FLUSH, IN LIEU OF PUNCHED 2" BRASS CAP IN CONC., DOWN 1.1' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-830. STATION IS LOCATED AT CENTERLINE INTER OF MACARTHUR BLVD. AND VON KARMAN AVE.

