

GPS #: **6175R2**

Date Destroyed:

Date Revised: 3/25/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/G-1

City / Location: Irvine

Scale Factor: 0.99997004

Ellipsoid Red. Factor: 1.00000348

Combination Factor: 0.99997352

Convergence Angle: -00 53 10.35061

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 27.13701	117 51 45.72990	2186676.250	6070939.374	
2007.00	33 39 27.15340	117 51 45.74668	2186677.93	6070937.98	

References: PMB 114/22-24, RSB 150/10-23, CR 2001-0832, CR 2013-0201, CR 2013-2218, CR 2013-2339, CR 2013-3383

Description:

FD MAG. NAIL AND WASHER, STAMPED "LS 5411" FLUSH PER CR 2013-3383, IN LIEU OF PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "6175R1 3-01" FLUSH, ORIGINAL MONUMENT BEING PUNCHED ROUND HEAD SPIKE AND WASHER, (ILLEGIBLE). MONUMENT WAS RESET PER CORNER RECORD # 2001-832. STATION IS LOCATED AT CENTERLINE INTER OF MACARTHUR BLVD. AND JAMBOREE RD.

