

GPS #: 6181

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/E-1

City / Location: Irvine

Scale Factor: 0.99997013

Ellipsoid Red. Factor: 0.99999846

Combination Factor: 0.99996859

Convergence Angle: -00 51 09.14198

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 39 30.59228 | 117 48 05.15706 | 2186742.579 | 6089587.007 | 32.188 |
| 2007.00 | 33 39 30.60901 | 117 48 05.17367 | 2186744.29 | 6089585.63 | |

References: RSB 109/48-49, RSB 150/10-23

Description:

FD PUNCHED 3 1/4" BRASS DISK, STAMPED "LS 4215", DOWN 1.2' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF UNIVERSITY DR. AND MICHELSON DR.

