

GPS #: **6188**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/J-1

City / Location: Irvine

Scale Factor: 0.99996990

Ellipsoid Red. Factor: 1.00000395

Combination Factor: 0.99997385

Convergence Angle: -00 52 37.68687

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 21.88152	117 50 46.28913	2186067.777	6075955.056	-82.615
2007.00	33 39 21.89795	117 50 46.30595	2186069.46	6075953.66	

References: MM 535/36-37, RSB 150/10-23

Description:

FD PUNCHED 2 1/2" O.C.S. ALUMINUM CAP, STAMPED "6-75", DOWN 1.7' IN O.C.S. WELL MONUMENT. STATION IS LOCATED AT CENTERLINE B.C. OF CAMPUS DR., 599.97' W'LY FROM ITS INTER WITH UNIVERSITY DR.

