

**GPS #:** **6192**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/C-2

City / Location: Newport Beach

Scale Factor: 0.99996928

Ellipsoid Red. Factor: 1.00000192

Combination Factor: 0.99997121

Convergence Angle: -00 54 07.97851

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 59.13445	117 53 30.59986	2183984.457	6062031.432	-40.213
2007.00	33 38 59.15088	117 53 30.61665	2183986.14	6062030.04	

References: PMB 38/14, RSB 150/10-23, 2016-2138A

**Description:**

FD PUNCHED 2" BRASS DISK IN CONC., DOWN 0.9' IN WELL MONUMENT WITH "WATER" MARKED ON LID. STATION IS LOCATED AT CENTERLINE INTER OF SANTA ISABEL AVE. AND IRVINE AVE.

