

GPS #: **6193R1**

Date Destroyed:

Date Revised: 12/4/2006

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/C-2

City / Location: Costa Mesa

Scale Factor: 0.99996967

Ellipsoid Red. Factor: 1.00000294

Combination Factor: 0.99997261

Convergence Angle: -00 54 13.91727

*Factors and Convergence Angle based on
the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 13.42166	117 53 41.40708	2185442.821	6061140.732	
2007.00	33 39 13.43806	117 53 41.42387	2185444.50	6061139.34	

References: MM 427/15-16, RSB 150/10-23, CR 2002-1598, CR 2003-0211

Description:

FD PK NAIL WITH "LS 5411" TAG IN LIEU OF LARGE PK NAIL AND WASHER, STAMPED "RCE 6579 COSTA MESA". MONUMENT WAS RESET PER CORNER RECORD # 2003-0211. STATION IS LOCATED AT CENTERLINE INTER OF BRENTWOOD ST. AND SANTA ANA AVE.

