

GPS #: **6200R1**

Date Destroyed:

Date Revised: 4/19/2001

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 919/F-3

City / Location: Newport Beach

Scale Factor: 0.99996460

Ellipsoid Red. Factor: 1.00000094

Combination Factor: 0.99996554

Convergence Angle: -00 53 26.32197

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 47.00312	117 52 14.79420	2164466.150	6068137.050	
2007.00	33 35 47.01942	117 52 14.81154	2164467.82	6068135.61	

References: RSB 150/10-23, CR 2001-836, CR 2002-0911

Description:

FD LARGE PK NAIL AND ALUMINUM WASHER STAMPED "CALTRANS" FLUSH, IN LIEU OF ROUND HEAD SPIKE AND WASHER (NO STAMPING), DOWN 0.3'. MONUMENT WAS RESET PER CORNER RECORD # 2001-836. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF MARGUERITE AVE. AND PACIFIC COAST HWY.

