

**GPS #:** 6207

Date Destroyed:  
Date Revised: 8/8/2006  
Benchmark Designation:  
OCS Index Map: 5LA  
Page/Grid: 889/C-3  
City / Location: Newport Beach

Scale Factor: 0.99996858  
Ellipsoid Red. Factor: 1.00000239  
Combination Factor: 0.99997098  
Convergence Angle: -00 54 13.83327

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 32.54865	117 53 41.25421	2181311.710	6061088.481	-50.016
2007.00	33 38 32.56504	117 53 41.27100	2181313.39	6061087.09	

References: RSB 150/10-23, CR 2005-1268

**Description:**

FD PUNCHED 2" BRASS DISK IN CONC., DOWN 1.0' IN WELL MONUMENT WITH "WATER" MARKED ON LID. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF IRVINE AVE. AND SANTIAGO DR.

