

GPS #: **6213R2**

Date Destroyed:

Date Revised: 10/19/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/A-2

City / Location: Irvine

Scale Factor: 0.99996910

Ellipsoid Red. Factor: 1.00000199

Combination Factor: 0.99997109

Convergence Angle: -00 52 16.12908

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 52.16018	117 50 07.05871	2183013.314	6079225.118	
2007.00	33 38 52.17663	117 50 07.07557	2183015.00	6079223.72	

References: RSB 150/10-23, CR 2001-0835, CR 2014-0217, CR 2014-1898

Description:

FD GEAR SPIKE AND WASHER STAMPED "PLS 7564" PER CR 2014-1898 IN LIEU OF GEAR SPIKE AND 1 3/4" ALUMINUM WASHER STAMPED "LS 4215 JOHNSON FRANK & ASSOC." FLUSH, ORIGINAL MONUMENT BEING CONC. NAIL. MONUMENT WAS RESET PER CORNER RECORD # 2001-835. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF BERKELEY AVE. AND CAMPUS DR.

