

GPS #: 6222

Date Destroyed: 4/24/1998

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/G-4

City / Location: Irvine

Scale Factor: 0.99996816

Ellipsoid Red. Factor: 1.00000131

Combination Factor: 0.99996947

Convergence Angle: -00 52 56.78267

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 16.09686	117 51 21.03923	2179464.197	6072915.587	-27.451
2007.00	33 38 16.11330	117 51 21.05607	2179465.88	6072914.19	

References: RSB 150/10-23

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 1" I.P. WITH PLUG AND TACK, FLUSH. STATION IS LOCATED AT BONITA CANYON RD., 0.5 MILE SE OF MACARTHUR BLVD., 20'+/- NORTH OF N'LY EDGE OF PAVEMENT, ON TOP OF 15'+/- SLOPE, S'LY OF DIRT RD., NE'LY OF CHRISTMAS TREE FARM.