

GPS #: **6231R2**

Date Destroyed:

Date Revised: 5/21/2009

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 888/G-3

City / Location: Costa Mesa

Scale Factor: 0.99996867

Ellipsoid Red. Factor: 1.00000085

Combination Factor: 0.99996952

Convergence Angle: -00 55 44.56458

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 35.85997	117 56 26.36508	2181869.635	6047136.774	
2007.00	33 38 35.87640	117 56 26.38189	2181871.32	6047135.38	

References: MM 518/18-19, RSB 150/10-23, CR 2003-1666, CR 2008-0487, CR 2008-1195

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH IN LIEU OF (6231R1) GEAR SPIKE AND WASHER STAMPED "LS 6970", ORIGINAL MONUMENT BEING PUNCHED 2" O.C.S. BRASS CAP, STAMPED "12-79", DOWN 1.7' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF 19TH ST. AND WHITTIER AVE.

