

GPS #: 6240R2

Date Destroyed:

Date Revised: 7/28/2009

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/E-5

City / Location: Newport Beach

Scale Factor: 0.99996755

Ellipsoid Red. Factor: 0.99999967

Combination Factor: 0.99996722

Convergence Angle: -00 53 33.57890

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 52.21443	117 52 28.00024	2177138.172	6067217.298	
2007.00	33 37 52.23082	117 52 28.01718	2177139.85	6067215.89	

References: RSB 150/10-23, CR 2003-1795B, PM 2008-111

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "LS 7077" PER PM 2008-111 IN LIEU OF PUNCHED SPIKE AND WASHER STAMPED "LS 4212 GPS NO, 6240 RESET", ORIGINAL MONUMENT BEING CONC. NAIL 14.5' E'LY FROM A WELL MONUMENT. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF JAMBOREE RD. AND EAST BLUFF/FORD DR.

