

GPS #: 6242R1

Date Destroyed: 6/2/2014
Date Revised: 6/13/2014
Benchmark Designation:
OCS Index Map: 5LA
Page/Grid: 889/H-5
City / Location: Newport Beach

Scale Factor: 0.99996717
Ellipsoid Red. Factor: 0.99999488
Combination Factor: 0.99996205
Convergence Angle: -00 52 46.09633

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 36.74575	117 51 01.59249	2175461.817	6074498.510	
2007.00	33 37 36.76209	117 51 01.60945	2175463.49	6074497.10	

References: RSB 150/10-23, CR 2001-1091, RS 2012-1035

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "6242R1 5-01" FLUSH, IN LIEU OF CONC. NAIL. MONUMENT WAS RESET PER CORNER RECORD # 2001-1091. STATION IS LOCATED AT THE VISUAL CENTERLINE INTER OF FORD RD. AND SAN MIGUEL DR.

