

GPS #: 6247

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/H-6

City / Location: Newport Beach

Scale Factor: 0.99996664

Ellipsoid Red. Factor: 0.99999204

Combination Factor: 0.99995868

Convergence Angle: -00 52 48.99818

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 15.16314	117 51 06.87321	2173287.386	6074018.521	166.276
2007.00	33 37 15.17948	117 51 06.89030	2173289.06	6074017.10	

References: RSB 150/10-23, CR 2002-0239

Description:

FD PUNCHED 2" BRASS DISK, STAMPED "LS 3109", DOWN 1.0' IN WELL MONUMENT WITH "WATER" LID. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF SAN MIGUEL DR. AND SPYGLASS HILL RD.

