

GPS #: 6255

Date Destroyed:

Date Revised: 3/18/2008

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/A-5

City / Location: Costa Mesa

Scale Factor: 0.99996773

Ellipsoid Red. Factor: 1.00000096

Combination Factor: 0.99996869

Convergence Angle: -00 54 54.52300

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 59.06565	117 54 55.30051	2178027.078	6054775.141	-20.118
2007.00	33 37 59.08218	117 54 55.31740	2178028.77	6054773.74	

References: RSB 150/10-23, CR 2007-1929

Description:

FD PUNCHED ROUND HEAD SPIKE WITH WASHER, STAMPED "RCE 22388", FLUSH PER CR 2007-1929. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF 17th ST. AND SANTA ANA AVE.

