

GPS #: **6264**

Date Destroyed: **1/6/2003**

Date Revised: **1/6/2003**

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/A-6**

City / Location: **Newport Beach**

Scale Factor: **0.99996681**

Ellipsoid Red. Factor: **1.00000148**

Combination Factor: **0.99996830**

Convergence Angle: **-00 54 52.29728**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 22.26229	117 54 51.25018	2174302.042	6055058.185	-30.991
2007.00	33 37 22.27868	117 54 51.26711	2174303.72	6055056.78	

References: **PMB 142/34-35, RSB 150/10-23**

Description:

(DESTROYED NOTE) - WELL MONUMENT
CURRENTLY IN INTERSECTION IS NOT GPS # 6264.
THIS WELL MONUMENT DIFFERS IN POSITION BY
1.03' +/- IN A NORTHERLY DIRECTION. ORIGINAL
WELL MONUMENT WAS DESTROYED BEING A FD
PUNCHED 2" BRASS CAP, DOWN 0.9' IN WELL
MONUMENT. STATION IS LOCATED AT THE
CENTERLINE INTER OF IRVINE AVE. AND 15th ST.

NO
LOCATION
MAP