

**GPS #:** 6269

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/F-7

City / Location: Newport Beach

Scale Factor: 0.99996638

Ellipsoid Red. Factor: 0.99999485

Combination Factor: 0.99996123

Convergence Angle: -00 53 25.75903

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 37 04.36225 | 117 52 13.76979 | 2172283.192   | 6068345.216  | 107.556               |
| 2007.00          | 33 37 04.37862 | 117 52 13.78695 | 2172284.87    | 6068343.79   |                       |

References: MM 527/31-35, RSB 150/10-23

**Description:**

FD PUNCHED 2" BRASS CAP, DOWN 0.9' IN WELL MONUMENT WITH "WATER" LID. STATION IS LOCATED AT CENTERLINE INTER OF SAN JOAQUIN HILLS RD. AND SANTA ROSA DR./BIG CANYON DR.

