

GPS #: 6271

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/G-7

City / Location: Newport Beach

Scale Factor: 0.99996614

Ellipsoid Red. Factor: 0.99999244

Combination Factor: 0.99995858

Convergence Angle: -00 52 58.63664

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 54.17988	117 51 24.41305	2171189.499	6072502.780	157.926
2007.00	33 36 54.19617	117 51 24.43015	2171191.17	6072501.36	

References: MM 378/32-37, RSB 150/10-23, CR 2002-0238

Description:

FD PUNCHED 2" BRASS CAP, DOWN 1.5' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF SAN MIGUEL DR. AND YACHT COQUETTE.

