

GPS #: **6273**

Date Destroyed:

Date Revised: 7/11/2011

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 919/A-1

City / Location: Newport Beach

Scale Factor: 0.99996535

Ellipsoid Red. Factor: 1.00000522

Combination Factor: 0.99997057

Convergence Angle: -00 54 53.48520

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 20.42566	117 54 53.41194	2168055.398	6054775.610	-109.111
2007.00	33 36 20.44206	117 54 53.42904	2168057.08	6054774.19	

References: MM 13/36-37, RSB 150/10-23, CR 2003-0347, CR 2011-0081

Description:

FD LEAD AND NAIL SET IN 6"x 5" ROCK DOWN 1.6' IN WELL MONUMENT. STATION IS LOCATED AT OLD CENTERLINE OF EAST BALBOA BLVD. AND 11th ST.

