

GPS #: **6283R1**

Date Destroyed:

Date Revised: 3/18/2008

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 888/J-7

City / Location: Newport Beach

Scale Factor: 0.99996637

Ellipsoid Red. Factor: 1.00000485

Combination Factor: 0.99997122

Convergence Angle: -00 55 02.29141

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 03.96360	117 55 09.43728	2172477.253	6053490.839	
2007.00	33 37 03.98005	117 55 09.45427	2172478.94	6053489.43	

References: RSB 150/10-23, CR 2001-0844, CR 2007-2504

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "6283R1 3-01" FLUSH PER CR 2007-2504, IN LIEU OF BRASS NAIL IN LEAD IN CONC. MONUMENT WAS RESET PER CORNER RECORD # 2001-844. STATION IS LOCATED AT THE VISUAL CENTERLINE PACIFIC COAST HWY. AT E.C. NEAR ST. ADDRESS 2000 PACIFIC COAST HWY.

