

GPS #: 6288

Date Destroyed:
Date Revised: 7/20/2010
Benchmark Designation:
OCS Index Map: 5LA
Page/Grid: 888/J-7
City / Location: Newport Beach

Scale Factor: 0.99996619
Ellipsoid Red. Factor: 1.00000490
Combination Factor: 0.99997109
Convergence Angle: -00 55 10.71089

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 56.33694	117 55 24.75890	2171727.231	6052182.938	-102.332
2007.00	33 36 56.35333	117 55 24.77596	2171728.91	6052181.52	

References: PMB 146/26-27, RSB 150/10-23, CR 2010-0801

Description:

FD PUNCHED 2" BRASS DISK IN CONC., DOWN 1.0' IN WELL MONUMENT, 10.15' SE'LY FROM ANOTHER WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF VIA ANTIBES (EAST) AND VIA LIDO SOUD.

