

GPS #: **6289**

Date Destroyed: **7/26/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LA**

Page/Grid: **889/C-7**

City / Location: **Newport Beach**

Scale Factor: **0.99996589**

Ellipsoid Red. Factor: **1.00000208**

Combination Factor: **0.99996797**

Convergence Angle: **-00 54 05.96724**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 43.61590	117 53 26.93980	2170283.209	6062125.244	-43.547
2007.00	33 36 43.63230	117 53 26.95694	2170284.89	6062123.82	

References: MM 190/43-44, RSB 150/10-23

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" BRASS DISK, DOWN 1.1' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE E.C. OF JAMBOREE RD., 211.08' S'LY OF PACIFIC COAST HWY.