

GPS #: 6292

Date Destroyed:

Date Revised: 4/27/2000

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 919/F-2

City / Location: Newport Beach

Scale Factor: 0.99996487

Ellipsoid Red. Factor: 0.99999905

Combination Factor: 0.99996391

Convergence Angle: -00 53 19.74782

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 59.06466	117 52 02.83074	2165669.448	6069167.799	19.934
2007.00	33 35 59.08098	117 52 02.84804	2165671.12	6069166.36	

References: PMB 274/11-12, RSB 150/10-23

Description:

FD PUNCHED 2" BRASS CAP, DOWN 1.1' IN WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF MARGUERITE AVE. AND 5' SOUTHWESTERLY OF THE CENTERLINE OF 5th AVE.

