

GPS #: 6295R1

Date Destroyed:

Date Revised: 8/6/2013

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 919/E-2

City / Location: Newport Beach

Scale Factor: 0.99996514

Ellipsoid Red. Factor: 1.00000158

Combination Factor: 0.99996672

Convergence Angle: -00 53 41.02670

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 11.29687	117 52 41.55356	2166956.683	6065912.169	
2007.00	33 36 11.31323	117 52 41.57087	2166958.36	6065910.73	

References: MM 444/16-17, RSB 150/10-23, CR 2001-0845, CR 2008-0412

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "6295R1 4-01" FLUSH PER CR 2008-0412, IN LIEU OF PUNCHED 2" BRASS CAP IN CONC., DOWN 1.3' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-845. STATION IS LOCATED AT CENTERLINE INTER OF AVOCADO AND 2nd ST.

