

**GPS #:** 6295R2

Date Destroyed:

Date Revised: 6/6/2014

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 919/E-2

City / Location: Newport Beach

Scale Factor: 0.99996514

Ellipsoid Red. Factor: 1.00000158

Combination Factor: 0.99996672

Convergence Angle: -00 53 41.02670

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 11.29687	117 52 41.55356	2166956.683	6065912.169	
2007.00	33 36 11.31323	117 52 41.57087	2166958.36	6065910.73	

References: MM 444/16-17, RSB 150/10-23, CR 2001-0845, CR 2008-0412, PM 2012-156

## Description:

FD 8" SPIKE WITH ALUMINUM DISK STAMPED "RCE 25742", FLUSH PER PM 2012-156 IN LIEU OF PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "6295R1 4-01" FLUSH PER CR 2008-0412, ORIGINAL MONUMENT BEEING PUNCHED 2" BRASS CAP IN CONC., DOWN 1.3' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-845. STATION IS LOCATED IN THE INTERSECTION OF AVOCADO AND 2ND ST.

