

**GPS #:** **6301R2**

Date Destroyed:

Date Revised: 7/17/2011

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 918/H-1

City / Location: Newport Beach

Scale Factor: 0.99996585

Ellipsoid Red. Factor: 1.00000518

Combination Factor: 0.99997102

Convergence Angle: -00 55 23.12149

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 36 41.91629 | 117 55 47.34340 | 2170300.515   | 6050249.760  |                       |
| 2007.00          | 33 36 41.93274 | 117 55 47.36051 | 2170302.20    | 6050248.34   |                       |

References: RSB 86/38, RSB 150/10-23, CR 2002-0821, CR 2010-0327, CR 2011-1098

**Description:**

FD GEAR SPIKE WITH TAG STAMPED "6965" IN LIEU OF PUNCHED SPIKE AND WASHER STAMPED "CNB", FLUSH IN AC, ORIGINAL MONUMENT BEING PUNCHED ROUND SPIKE WITH WASHER (NO STAMPING), DOWN 0.2' IN A.C. STATION IS LOCATED AT CENTERLINE INTER OF WEST BALBOA BLVD. AND 26th ST. (NW). MONUMENT IS ALSO NORTHWESTERLY 0.84' FROM ANOTHER MONUMENT OF SAME CHARACTER.

