

GPS #: 6499

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 860/F-3

City / Location: Irvine

Scale Factor: 0.99997398

Ellipsoid Red. Factor: 1.00000125

Combination Factor: 0.99997523

Convergence Angle: -00 50 39.71124

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 43.43113	117 47 11.59965	2200101.456	6094311.433	-26.043
2007.00	33 41 43.44767	117 47 11.61634	2200103.15	6094310.05	

References: MM 277/27-30, RSB 150/24-35

Description:

FD CONC. NAIL AND 3/4" BRASS TAG (ILLEGIBLE) DOWN 1.5' IN O.C.S. WELL MONUMENT, ACCEPTED AS BRASS TAG STAMPED "RCE 13703" PER MM 277/27-30, LOCATED AT THE CENTERLINE INTER OF ROXBURY DR. AND GROVEVIEW LN.

