

GPS #: 6503R1

Date Destroyed:

Date Revised: 9/17/2007

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/C-1

City / Location: Unin., Orange County

Scale Factor: 0.99997486

Ellipsoid Red. Factor: 0.99998903

Combination Factor: 0.99996389

Convergence Angle: -00 48 52.61651

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 12.05905	117 43 56.71104	2202756.516	6110817.247	
2007.00	33 42 12.07552	117 43 56.72702	2202758.20	6110815.92	

References: RSB 122/6-9, RSB 150/24-35, CR 2005-0403, CR2007-1119

Description:

FD SPIKE & WASHER STAMPED "LS 6086", FLUSH. IN LIEU OF PUNCHED 2 1/2" O.C.S. BRASS DISK, STAMPED "10-88", DOWN 1.25' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD 2007-1119. STATION IS LOCATED AT CENTERLINE B.C. OF BEE CANYON ACCESS RD., 2442.04' NE'LY FROM INTERSECTION OF SAND CANYON AVE. AND IRVINE BLVD.

