

GPS #: **6504**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **5LB**

Page/Grid: **861/C-1**

City / Location: **Unin., Orange County**

Scale Factor: **0.99997555**

Ellipsoid Red. Factor: **0.99998980**

Combination Factor: **0.99996535**

Convergence Angle: **-00 48 59.03042**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 33.80329	117 44 08.38293	2204968.257	6109862.580	213.175
2007.00	33 42 33.81976	117 44 08.39883	2204969.94	6109861.26	

References: RSB 122/6-9, RSB 150/24-35

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED 2 1/2" O.C.S. BRASS DISK, STAMPED "10-88", DOWN 1.16' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE END OF CURVE OF BEE CANYON ACCESS RD., 0.9 MILE FROM INTER OF SAND CANYON AVE. AND IRVINE BLVD.