

GPS #: 6505

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/D-7

City / Location: Unin., Orange County

Scale Factor: 0.99997648

Ellipsoid Red. Factor: 0.99998272

Combination Factor: 0.99995920

Convergence Angle: -00 48 47.21237

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 02.90375	117 43 46.87671	2207883.635	6111720.936	361.069
2007.00	33 43 02.92024	117 43 46.89257	2207885.32	6111719.62	

References: RSB 122/6-9, RSB 150/24-35, CR 2012-1571, CR 2012-2756

Description:

FD PUNCHED 2 1/2" O.C.S. BRASS DISK, STAMPED "10-88", DOWN 1.39' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE END OF CURVE OF BEE CANYON ACCESS RD., 1.70 MILES FROM INTER OF SAND CANYON AVE. AND IRVINE BLVD.

