

GPS #: 6510R1

Date Destroyed:

Date Revised: 9/18/2007

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/G-3

City / Location: Tustin

Scale Factor: 0.99997925

Ellipsoid Red. Factor: 0.99999605

Combination Factor: 0.99997530

Convergence Angle: -00 50 16.01135

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 26.06524	117 46 28.47111	2216485.475	6098195.395	
2007.00	33 44 26.08141	117 46 28.48722	2216487.13	6098194.06	

References: MM 601/1-20, RSB 150/24-35, CR 2007-1046, CR 2007-1681

Description:

FD. MAG NAIL AND WASHER STAMPED "LS 6790" IN LIEU OF GEAR SPIKE AND WASHER STAMPED "RCE 23956", FLUSH, WITH FOUR 2' CONC. NAIL TANGENT OVER TIES. MONUMENT WAS RESET PER CR 2007-1681. STATION IS LOCATED AT CENTERLINE INTERSECTION OF JAMBOREE RD. AND CHAMPION WAY, 1.0 MILE NE FROM THE INTERSECTION OF JAMBOREE RD. AND IRVINE BLVD.

