

GPS #: 6512

Date Destroyed:

Date Revised: 8/16/2004

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/H-1

City / Location: Tustin

Scale Factor: 0.99998105

Ellipsoid Red. Factor: 0.99999061

Combination Factor: 0.99997166

Convergence Angle: -00 49 57.93476

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 17.54382	117 45 55.57575	2221647.994	6101048.661	196.286
2007.00	33 45 17.55999	117 45 55.59180	2221649.65	6101047.33	

References: MM 644/1-20, RSB 150/24-35

Description:

FD 1" I.P. WITH PLASTIC TAG "LS 5780", DOWN 0.4'. STATION IS LOCATED FROM INTER OF JAMBOREE RD. AND TUSTIN RANCH RD., 0.5 MILE NE'LY ON JAMBOREE RD., 505' +/- N'LY OF OCSBM 3G-36-91, 8.5' BACK FROM BACK OF CURB AND 2.5' TOWARDS JAMBOREE FROM THE FRONT OF CONC. WALK. IN THE PLANTER AREA BETWEEN CURB AND SIDEWALK.

