

GPS #: 6513

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 800/J-6

City / Location: Tustin

Scale Factor: 0.99998348

Ellipsoid Red. Factor: 0.99997697

Combination Factor: 0.99996045

Convergence Angle: -00 49 46.05910

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 24.49260	117 45 33.96468	2228388.178	6102971.137	481.302
2007.00	33 46 24.50885	117 45 33.98081	2228389.84	6102969.80	

References: MM 644/1-20, RSB 150/24-35

Description:

FD 2" I.P. TAGGED "LS 5780" DOWN 0.8'. STATION IS LOCATED AT CENTERLINE B.C. OF JAMBOREE RD., 1.85 MILES NE'LY FROM THE INTER OF JAMBOREE RD. AND TUSTIN RANCH RD.

