

GPS #: 6530

Date Destroyed:

Date Revised: 5/3/2004

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 859/J-1

City / Location: Santa Ana

Scale Factor: 0.99997512

Ellipsoid Red. Factor: 1.00000312

Combination Factor: 0.99997824

Convergence Angle: -00 52 31.74488

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 20.33027	117 50 35.47601	2204089.342	6077144.581	-65.259
2007.00	33 42 20.34677	117 50 35.49291	2204091.03	6077143.18	

References: PMB 48/34, RSB 150/24-35, CR 2010-1995, CR 2012-1706

Description:

FD PUNCHED 3" OCS BRASS DISK STAMPED "9 / 9 / 9 / 9" (SEE MONUMENT RECORD FOR STAMPING) DOWN 0.98' IN WELL MONUMENT. STATION IS LOCATED ON CENTERLINE OF REDHILL AVE., 30' E'LY FROM THE CENTERLINE INTER OF RED HILL AVE. AND BARRANCA PKWY.

