

**GPS #:** 6532

Date Destroyed:

Date Revised: 5/21/2009

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 859/H-3

City / Location: Irvine

Scale Factor: 0.99997397

Ellipsoid Red. Factor: 1.00000375

Combination Factor: 0.99997771

Convergence Angle: -00 52 52.14953

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 43.01956	117 51 12.60798	2200366.475	6073949.994	-78.320
2007.00	33 41 43.03591	117 51 12.62465	2200368.15	6073948.61	

References: PMB 219/34-35, RSB 150/24-35, CR 2008-1267

**Description:**

FD PUNCHED 2 1/4" BRASS DISK, STAMPED "LS-2528" DOWN 1.37' IN WELL MONUMENT WITH FOUR 2' TANGENT OVER CONC. NAIL AND TIN TIES. STATION IS LOCATED ALONG THE CENTERLINE OF REYNOLDS AVE., 0.02' NW'LY FROM ITS CENTERLINE INTER WITH RED HILL AVE.

