

GPS #: 6533

Date Destroyed:

Date Revised: 1/15/2013

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 859/G-4

City / Location: Irvine

Scale Factor: 0.99997330

Ellipsoid Red. Factor: 1.00000394

Combination Factor: 0.99997724

Convergence Angle: -00 53 03.72165

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 21.04396	117 51 33.66664	2198172.848	6072136.642	-82.355
2007.00	33 41 21.06040	117 51 33.68355	2198174.53	6072135.24	

References: PMB 204/21-32, RSB 150/24-35, CR 2011-1738, CR 2012-1669

Description:

FD PUNCHED 2 1/4" BRASS DISK, STAMPED "LS-3246" DOWN 1.57' IN WELL MONUMENT WITH FOUR 2' PUNCHED SPIKE TANGENT OVER TIES, STATION IS LOCATED AT CENTERLINE B.C. OF SKY PARK CIR., 50'+/- E'LY OF THE NE'LY CORNER OF EXECUTIVE AIRPORT PARKING LOT, OPPOSITE LENTREX INTERNATIONAL BUILDING (18001 SKY PARK BLVD.).

