

**GPS #:** 6537

Date Destroyed:

Date Revised: 5/3/2004

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/C-6

City / Location: Tustin

Scale Factor: 0.99997716

Ellipsoid Red. Factor: 1.00000158

Combination Factor: 0.99997874

Convergence Angle: -00 51 34.56016

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 23.90661	117 48 51.41254	2210381.878	6086031.411	-33.002
2007.00	33 43 23.92313	117 48 51.42918	2210383.57	6086030.03	

References: MM 258/37-38, RSB 150/24-35

## Description:

FD PUNCHED 3 1/2" BRASS CAP, STAMPED "45 / 45" (SEE MONUMENT RECORD FOR STAMPING) DOWN 1.80' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF BROWNING AVE. AND WALNUT AVE.

