

GPS #: **6548R1**

Date Destroyed:

Date Revised: 9/18/2007

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/F-4

City / Location: Tustin

Scale Factor: 0.99997851

Ellipsoid Red. Factor: 0.99999954

Combination Factor: 0.99997805

Convergence Angle: -00 50 47.87723

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 04.38147	117 47 26.45996	2214365.860	6093266.524	
2007.00	33 44 04.39770	117 47 26.47605	2214367.52	6093265.19	

References: MM 673/1-6, RSB 150/24-35, CR 2007-1042, CR 2007-1677

Description:

FD. GEAR SPIKE AND WASHER STAMPED "LS 6970" IN LIEU OF GEAR SPIKE AND WASHER STAMPED "RCE 23956". MONUMENT WAS RESET PER CORNER RECORD 2007-1677. STATION IS LOCATED AT THE CENTERLINE INTERSECTION OF IRVINE BLVD. AND ROBINSON DR.

