

**GPS #:** **6550R1**

Date Destroyed:

Date Revised: 4/27/2001

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/D-7

City / Location: Tustin

Scale Factor: 0.99997660

Ellipsoid Red. Factor: 1.00000212

Combination Factor: 0.99997872

Convergence Angle: -00 51 22.23509

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 06.62950	117 48 28.98364	2208607.315	6087899.543	
2007.00	33 43 06.64605	117 48 29.00019	2208609.01	6087898.17	

References: RSB 150/24-35, CR 2001-0851

**Description:**

FD PUNCHED SPIKE AND WASHER STAMPED "LS 5411" FLUSH, IN LIEU OF SPIKE AND TIN. MONUMENT WAS RESET PER CORNER RECORD # 2001-0851. STATION IS LOCATED 1.98' SE'LY FROM A WELL MONUMENT THAT IS THE CENTERLINE POINT OF INTER OF A CURVE (PER MM 346/19-24) ON CHAMBERS AVE., 570'+/- SE'LY FROM THE INTER OF CHAMBERS AVE. AND FRANKLIN AVE.

