

GPS #: 6551

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 830/C-7

City / Location: Tustin

Scale Factor: 0.99997607

Ellipsoid Red. Factor: 1.00000257

Combination Factor: 0.99997865

Convergence Angle: -00 51 29.29158

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 50.37796	117 48 41.82490	2206980.999	6086790.376	-53.760
2007.00	33 42 50.39446	117 48 41.84159	2206982.69	6086788.99	

References: MM 530/40-41, RSB 150/24-35

Description:

FD PUNCHED 2" BRASS DISK STAMPED "LS 3246", DOWN 1.30' IN WELL MONUMENT WITH FOUR 2' CONC. NAIL AND TIN TIES. STATION IS LOCATED AT CENTERLINE INTER OF FRANKLIN AVE. AND DOW AVE.

