

**GPS #:** 6554

Date Destroyed:

Date Revised: 6/20/2013

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 859/J-4

City / Location: Irvine

Scale Factor: 0.99997291

Ellipsoid Red. Factor: 1.00000378

Combination Factor: 0.99997669

Convergence Angle: -00 52 26.07347

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 41 07.88204 | 117 50 25.15532 | 2196753.766   | 6077904.695  | -79.042               |
| 2007.00          | 33 41 07.89848 | 117 50 25.17213 | 2196755.45    | 6077903.30   |                       |

References: MM 305/40-42, RSB 150/24-35, CR 2013-0177

## Description:

FD 2 1/2" BRASS CAP, STAMPED "LS 3246", DOWN 1.37' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF KELVIN AVE. AND DERIAN AVE.

