

**GPS #:** **6573**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 860/E-2

City / Location: Irvine

Scale Factor: 0.99997489

Ellipsoid Red. Factor: 1.00000252

Combination Factor: 0.99997742

Convergence Angle: -00 51 06.25615

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 13.07723	117 47 59.90553	2203158.186	6090275.001	-52.690
2007.00	33 42 13.09379	117 47 59.92228	2203159.88	6090273.61	

References: RSB 88/27-33, RSB 150/24-35, CR 2005-0360

**Description:**

FD PUNCHED 1/2" HEX BRASS CAP, DOWN 1.34' IN WELL MONUMENT. STATION IS LOCATED ON HARVARD AVE., 1000'+/- NE'LY FROM INTER WITH DEERFIELD AVE. AND 75' SW'LY OF RAILRD. TRACK CENTERLINE.

