

GPS #: 6601

Date Destroyed:

Date Revised: 4/27/2001

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 860/E-4

City / Location: Irvine

Scale Factor: 0.99997271

Ellipsoid Red. Factor: 1.00000121

Combination Factor: 0.99997392

Convergence Angle: -00 51 02.30205

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 01.14374	117 47 52.70993	2195878.876	6090774.895	-25.312
2007.00	33 41 01.16041	117 47 52.72662	2195880.58	6090773.51	

References: MM 369/48-50, RSB 150/24-35

Description:

FD 3/4" BOLT AND WASHER, STAMPED "RCE 19249", FLUSH. STATION IS LOCATED AT CENTERLINE INTER OF MALLARD/MANDARIN AND CROSSCREEK.

