

GPS #: 6611

Date Destroyed:

Date Revised: 3/20/2000

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 860/H-2

City / Location: Irvine

Scale Factor: 0.99997460

Ellipsoid Red. Factor: 0.99999776

Combination Factor: 0.99997236

Convergence Angle: -00 50 04.34993

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 03.58465	117 46 07.24995	2202058.719	6099777.515	46.785
2007.00	33 42 03.60099	117 46 07.26602	2202060.39	6099776.18	

References: PMB 177/37-39, RSB 150/24-35, C.E.T.B. # 297

Description:

FD CONC. NAIL AND TIN, FLUSH. STATION IS LOCATED IN THE INTERSECTION OF TRABUCO RD. AND REMINGTON AVE., 2.00' NORTHERLY OF THE CENTERLINE INTERSECTION MONUMENT BEING A SPIKE AND WASHER. (MONUMENT IS ONE OF FOUR-TWO FOOT TIES.)

